

Plastic Case LCD Display



**Plastic LCD Monitor, 20.1"-1600x1200
CCFL-300nits,VGA+DVI+HDMI, Black Color
External Power Adapter, Power Code: Italy**

MODEL: EPC2010AHB-H-MD1

FEATURES:

- Elegant design with slim bezel
- Integrated amp and stereo speakers give you a complete multimedia experience
- Brilliant color and crystal-clear images and text


SPECIFICATIONS:

Panel	Cell Type / Glass Surface	TFT LCD / Black Anti-Glare, low reflection coating	
	Aspect Ratio / Size	4 : 3 / 20.1" viewable diagonal area	
	Active Area / Pixel Pitch	408.24(H) x 306.18(V) mm / 0.2916(H) x 0.2916(V) mm	
	Native Resolution / Colors	1600(H) x 1200(V) / 16.7 Million	
	Brightness / Contrast	300 cd/m ² (typ) / 1000 : 1	
	Response Time	≤ 5 ms	
	Viewing Angle (typical)	H. 170° (- 85° ~ + 85°) , V. 160° (- 80° ~ + 80°)	
	Light Source	LED , Long life, 35,000 hrs (typ)	
Input Sources	PC System	Signal	Analog RGB (0.7/1.0 V _{p-p} , 75 ohms)
		Sync	Separate Sync, Composite Sync, Sync On Green
		Frequency	F _H : 30 - 82Khz , F _V : 50 -75Hz
Audio System	2W speaker x 2		
Input Terminals	1 x VGA, 1 x HDMI, 1 x DVI, 1 x PC Audio (Stereo Headphone Jack) , 1 x DC Power Plug		
Convenient Features	Auto Calibration , Back Light Adjustment , Plug&Play (VESA DDC/CI, DDC 2B)		
	OSD Multi-Languages , Wall Mount Ready (VESA 100 x 100 mm)		
Power	12V DC-IN with external adapter		
Power Consumption	Operation / Power Saving	40 watt , < 5 watt (Support DPMS)	
Operating Condition	Temperature / Humidity	0°C ~ 50°C (32°F ~ 122°F) , 10% ~ 90% (no condensation)	
Storage Condition	Temperature / Humidity	- 20°C ~ 60°C (- 4°F ~ 140°F) , 10% ~ 90% (no condensation)	
Certification	FCC , CE		
Dimensions	Physical	With Base(W x H x D) : 460.0 x 453.42 x 190.0 mm	
		Without Base(W x H x D) : 460.0 x 380.0 x 58.6 mm	
	Carton	W x H x D = 560 x 463 x 205 mm	
Weight	N.W. / G.W.	6.7 Kgs / 7.7 Kgs	
Container Loaded	20ft / 40ft / 40ft HQ	TBD (Sets , By pallet)	
Options	Enhanced Panel	Video / TV	Others
	Panel with LED backlight	DVI	Digital Signage(Stand alone)
	High brightness panel	HDMI	Motion Sensor
	Wide Temperature	SV + AV + TV	Light Sensor
	Sun Light Readable		Auto-Dimming

**Specifications subject to change without notice, not responsible for typographical errors.*

MECHANICAL DRAWING:

This is subject to change without Notice. Final Drawings Will be Provided for Approval after Order.



Drawing No.: EPC2010AHB-H-MD1-05122023-V1